



GRASS VALLEY
A PLACE TO LIVE AND THRIVE

**CITY OF GRASS VALLEY
ENGINEERING DIVISION**

April 21, 2022

ADDENDUM NO. 1

**NOTICE TO CONTRACTORS,
SPECIAL PROVISIONS, AND
CONSTRUCTION CONTRACT**

AND

**PROPOSAL AND
BIDDER'S CERTIFICATES**

FOR

**CONDON AND SCOTTEN TURF REPLACEMENT PROJECT
PROJECT NO. 21-10**

BID OPENING – THURSDAY, APRIL 28, 2022, AT 3:30PM

**ALL ADDENDA MUST BE SIGNED AND RETURNED
WITH THE BIDDER'S PROPOSAL IN ORDER FOR THE
BID TO BE CONSIDERED RESPONSIVE.**

ADDENDUM NO. 1

**PROJECT: CONDON AND SCOTTEN TURF REPLACEMENT PROJECT
PROJECT NO. 21-10**

BID OPENING: THURSDAY, APRIL 28, 2022, AT 3:30PM

REVISIONS TO NOTICE TO CONTRACTORS:

1. Replace first paragraph of General Work Description with the following:

The scope of work, in general, includes; roadway and field excavation, grading and aggregate installation; drainage, concrete and fencing improvements, restroom construction and all preparatory work for the future installation of an artificial turf surfacing. Other related items not mentioned above, that are required by the plans, specifications or these Special Provisions shall be performed, placed, constructed, or installed.

REVISIONS TO SPECIAL PROVISIONS:

1. Add the following paragraph to Section 4-1.01, General:

Once the majority of contract work is completed, working days may be suspended or extended with the Engineer's approval, upon written request of the Contractor to the City of Grass Valley as necessary to complete work primarily associated with "Restroom Building" of these Special Provisions. Added working days will be justified by the contractor, subcontractor or supplier for schedule disruptions including restroom building design and permit approval, extended material and fixture lead times, and offsite prefab building construction, delivery and installation time.

2. Replace first paragraph of Section 10-1.01, Scope Of Work with the following:

The scope of work, in general, includes; roadway and field excavation, grading and aggregate installation; drainage, concrete and fencing improvements, restroom construction and all preparatory work for the future installation of an artificial turf surfacing. Other related items not mentioned above, that are required by the plans, specifications or these Special Provisions shall be performed, placed, constructed, or installed.

3. Add the following paragraph to Section 10-1.02, General Requirements:

The City will contract separately for the final installation of the artificial turf system. The contractor shall coordinate closely with the Engineer and the City's selected turf installer for any changes to drainage layouts and final grades, timing of improvements, finishing, testing, and preparing the site for turf system installation.

4. Remove Section 10-1.45, Artificial Turf Surfacing System.

REVISIONS TO CONSTRUCTION CONTRACT:

1. Replace Page 10 in its entirety with the attached Page 10.

REVISIONS TO PROPOSAL:

1. Replace Page 3 & 4 in its entirety with the attached Page 3 & 4.

REVISION TO PLANS:

1. Remove all references to turf system installation on plans. Contractor to complete all preparatory work as shown for turf installation, but will not be responsible to install artificial turf system (geofabric, shock pad, turf and infill)

END OF REVISIONS

Issued By:

Bjorn P. Jones, PE
City Engineer

4/21/22

Date

I HAVE READ AND UNDERSTAND THIS ADDENDUM

Signature

Bidder

ARTICLE 18: BID ITEMS

ITEM NO.	DESCRIPTION	UNIT OF MEAS	EST. QTY.	UNIT PRICE	TOTAL COST
1	Mobilization	LS	1		
2	Traffic Control System	LS	1		
3	Clearing, Grubbing and Removal	LS	1		
4	Abandon Existing Water Supply	EA	2		
5	Earthwork	LS	1		
6	Rock Dissipator	TN	20		
7	Drainage Pipe (8" PVC Perforated)	LF	2450		
8	Drainage Pipe (12" HDPE Solid)	LF	330		
9	Drainage Pipe (HDPE Flat Drain, Perforated)	LF	3200		
10	Sewer Pipe (4" PVC)	LF	75		
11	Sewer Cleanout and Backflow Preventer	EA	1		
12	Sewer Service Wye	EA	1		
13	Water Pipe (1" Poly)	LF	200		
14	Water Pipe (4" PVC)	LF	175		
15	Gate Valve and Box (4")	EA	1		
16	Water Main Tap and Saddle (1")	EA	1		
17	Irrigation Quick Connect	EA	2		
18	Aggregate Base	CY	900		
19	Minor Concrete (6" Edge Curb)	LF	2000		
20	Minor Concrete (9" Edge Curb)	LF	700		
21	Minor Concrete (6" Thickened Curb)	LF	420		
22	Minor Concrete (Sidewalk, Curb Ramp, Parking Slab)	SF	3800		
23	Detectable Warning Surface	EA	1		
24	Permeable Field Aggregate (4" Depth)	SY	22000		
25	Hot Mix Asphalt (3" Depth)	SY	150		
26	Decomposed Granite	TN	50		
27	Fiber Roll	LF	200		
28	Chain Link Fence (4' Perimeter)	LF	650		
29	Chain Link Fence (12' Freestanding)	LF	100		
30	Chain Link Gate (4' Wide)	EA	6		
31	Chain Link Gate (6' Wide)	EA	2		
32	Chain Link Gate (12' Wide)	EA	1		
33	Barrier Net System	LF	60		
34	Barrier Gate	LS	1		
35	Restroom Building	LS	1		
36	Roadside Sign	EA	3		
37	Painted Pavement Markings	LS	1		

TOTAL COST: \$ _____

Name of Contractor/Company

BID ITEMS
CONDON AND SCOTTEN TURF REPLACEMENT PROJECT
PROJECT NO. 21-10

ITEM NO	ITEM	UNIT OF MEAS	EST QTY	UNIT PRICE	ITEM TOTAL
1	Mobilization	LS	1		
2	Traffic Control System	LS	1		
3	Clearing, Grubbing and Removal	LS	1		
4	Abandon Existing Water Supply	EA	2		
5	Earthwork	LS	1		
6	Rock Dissipator	TN	20		
7	Drainage Pipe (8" PVC Perforated)	LF	2450		
8	Drainage Pipe (12" HDPE Solid)	LF	330		
9	Drainage Pipe (HDPE Flat Drain, Perforated)	LF	3200		
10	Sewer Pipe (4" PVC)	LF	75		
11	Sewer Cleanout and Backflow Preventer	EA	1		
12	Sewer Service Wye	EA	1		
13	Water Pipe (1" Poly)	LF	200		
14	Water Pipe (4" PVC)	LF	175		
15	Gate Valve and Box (4")	EA	1		
16	Water Main Tap and Saddle (1")	EA	1		
17	Irrigation Quick Connect	EA	2		
18	Aggregate Base	CY	900		
19	Minor Concrete (6" Edge Curb)	LF	2000		
20	Minor Concrete (9" Edge Curb)	LF	700		
21	Minor Concrete (6" Thickened Curb)	LF	420		
22	Minor Concrete (Sidewalk, Curb Ramp, Parking Slab)	SF	3800		
23	Detectable Warning Surface	EA	1		
24	Permeable Field Aggregate (4" Depth)	SY	22000		
25	Hot Mix Asphalt (3" Depth)	SY	150		
26	Decomposed Granite	TN	50		
27	Fiber Roll	LF	200		

28	Chain Link Fence (4' Perimeter)	LF	650		
29	Chain Link Fence (12' Freestanding)	LF	100		
30	Chain Link Gate (4' Wide)	EA	6		
31	Chain Link Gate (6' Wide)	EA	2		
32	Chain Link Gate (12' Wide)	EA	1		
33	Barrier Net System	LF	60		
34	Barrier Gate	LS	1		
35	Restroom Building	LS	1		
36	Roadside Sign	EA	3		
37	Painted Pavement Markings	LS	1		

TOTAL COST: \$ _____

Name of Contractor/Company

The foregoing quantities are approximate only, being given as a basis for comparison of bids, and the Engineering Department does not express or by implication agree that the actual amount of work will correspond therewith, but reserves the right to increase or decrease the amount of any class or portion of the work, or to omit portions of the work, as may be deemed necessary, or advisable by the Engineer.